DOOR & WINDOW TAKEOFF

PROJECT: HAIZE RESIDENCE **SHEET # 1 OF 1**

TAKEOFF BY: **DATE**

DOORS

HOW MANY	DOOR NO.	DOOR WIDTH	DOOR HEIGHT	DOOR THICKNESS	DOOR TYPE	DOOR MATERIAL	DOOR GLASS	FRAME TYPE	FRAME MATERIAL	JAMB SIZE	REMARKS
	1	3'0	6'8	1-3/4"	S/C	Birch	(2) 1'6" sidelights		Ponderosa Pine	4-1/4"	6'0x6'8 opening
	2	6'0	6'8		sliding	Glass	1/4" insulated		Aluminum	4-9/16"	includes screen
	3	2'8	6'8	1-3/8"	H/C	Birch			Ponderosa Pine	"	
	4	3'0	6'8	1-3/4"	S/C	"			"	"	4-1/4" jamb for door from garage to yard
	5	2'4	6'8	1-3/8"	H/C	"			"	"	
	6	7'0	8'0		overhead	wood			"	4-1/4"	Sectional Garage door
	7	2'6	6'8	1-3/8"	H/C	Birch			"	4-9/16"	Bypass type: 4 openings @ 5'0x6'8 each
											**Allow $200.00 for Exterior doors
											*** $250.00 allowance for all hardware

WINDOWS

HOW MANY	WINDOW NO.	WINDOW WIDTH	WINDOW HEIGHT	WINDOW THICKESS	WINDOW TYPE	FRAME MATERIAL	FRAME TYPE	JAMB SIZE	HEAD SIZE	SILL SIZE	REMARKS
	1	6'0	5'0		casement	wood					
	2	4'0	3'0		"	"					
	3	3'0	4'0		"	"					
	4	4'0	4'0		"	"					